Quercus robur

Prospective location of new access gate into retained grassland behind existing fence line. 2m mowed strip leading to gate.

1m width of grass verge on edge of carriageway to be mowed regularly as lawn.

Mowing regime of grass up to existing fence line changed to become less frequent and arisings lifted to reduce soil fertility and encourage wildflowers.

Retained area of grassland will be enhanced by plug planting of Devil's bit scabious, Ragged robin and Cuckoo flower. Grassland will be managed to encourage species diversity, with new gate access to area required for maintenance needs.

Prospective location of reptile hibernacula subject to ecologist detail

Area of existing amenity grass to be retained and managed in current regime, which provides easy access to utility covers and allows for informal play.

Alnus x spaethii

Fagus sylvatica

Quercus robur

MUGA
637sqm

3,355sqm

Play Area

PLANNING

Rev.	Date	Comment	Approved	Drawn
P03	10.04.2024	Removed /Retained trees update	SB	TK
P02	27.03.2024	Additional annotations	SB	GE
P01	26.03.2024	First issue	SB	GE

PRELIMINARY | PLANNING | DESIGN | TENDER | CONSTRUCTION

soltysbrewster

4 Stangate House
Stanwell Road
Penarth
Vale of Glamorgan
CF64 2AA

Telephone:- + 44(0) 33 0013 0012
e-mail:- enquiry@soltysbrewster.co.uk

client

Lawray Architects

project

Goetre Primary School

drawing title

South off-site habitat compensation sketch design

scale	drawn	approved	date
1:250 @ A1	GE	SB	Mar 2024

drawing no.

26CB01 - SBC - 00 - XX - DR - L - 0403
Project Originator Zone Level Type Role Number

revision

P03

Soltys Brewster Consulting is the trading name of Soltys Brewster Consulting Ltd. Registered Offices:- 4 Stangate House, Stanwell Road, Penarth, Vale of Glamorgan, CF64 2AA. Registration No. 6262312.
Dimensions should not be scaled from this drawing, only figured dimensions are to be used. All discrepancies or queries regarding this drawing should be referred to Soltys Brewster Consulting Ltd. Soltys Brewster Consulting Ltd accept no liability for any expense, loss or damage of whatever nature and however arising from variation made to this drawing or in the execution of the work to which it relates which has not been referred to them and their approval obtained.