SITE SURVEY

St.Tydfil Hospital
Upper Thomas Street
Merthyr Tydfil

Notes:

Survey Grid
Plane grid related to National Grid at survey point S3
:305078.365mE, 206352.578mN, 190.006m

Survey Datum :
Related to GPS Datum at survey point S3

Sheet 2 of 3	Surveyed By: P.M.S.
Datum	Drawn By: P.M.S.
See Notes Above for Datum North Point Approximate	Date of Survey: March 2020 Scale: 1:250
Client: St Tydfil's Developments LLP	Survey Job No. SS-1143C_2D

Revisions:

A	Tree locations adjacent to northern boundary wall of park added 24/03/20
B	Additional Survey of courtyard of front building added April 2020
C	Additional Survey of South Boundary lane / Park Area added August 2020

Legend:

AV	AIR VALVE	PGM	PERMANENT GROUND MARKER
B	BOLLARD	PRF	POST & RAIL FENCE
BL	BED LEVEL	PS	PAVING SLABS
BT	BRITISH TELECOM IC	PWF	POST & WIRE FENCE
BW	BRICK WALL	RE	RODDING EYE
BWF	BARBED WIRE FENCE	RL	RIDGE LEVEL
CATV	CABLE TV IC	RP	REFLECTOR POST
CBF	CLOSE BOARDED FENCE	RS	ROAD SIGN
CL	COVER LEVEL	RSJ	ROLLED STEEL JOIST
CLF	CHAIN LINK FENCE	RW	RETAINING WALL
CM	CABLE MARKER	RWP	RAIN WATER PIPE
CONC.	CONCRETE	SAP.	SAPLING
CP	CATCH PIT	SFL	SOFFIT LEVEL
CPF	CHESTNUT PALING FENCE	SL	SLT LEVEL
CSL	COVER SLAB LEVEL	SMH	SURFACE MANHOLE
(dilopi)	DILAPIDATED	SNP	STREET NAME PLATE
(dis)	DISUSED	SP	SIGN POST
DK	DROP KERB	ST	STAY(S)
DPC	DAMP PROOF COURSE	STCH.	STANCHION
DSW	DWARF STONE WALL	SV	STOP VALVE
EL	EAVES LEVEL	SVP	SOIL & VENT PIPE
ELEC.	ELECTRICITY	SW	STONE WALL
EP	ELECTRICITY POLE	TCB	TELEPHONE CALL BOX
FB	FLOWER BED	TEL	TELEPHONE
FFL	FINISHED FLOOR LEVEL	TL	TRAFFIC LIGHTS
FH	FIRE HYDRANT	TM	TARMAC
FL	FENCE LEVEL	TP	TELEGRAPH POLE
FMH	FOUL MAIN HOLE	TR	TRANSFORMER
FP	FLAG POLE	U/S	UNDERSIDE
G	GULLY	UTL	UNABLE TO LIFT
GV	GAS VALVE	VP	VENT PIPE
HR	HAND RAIL	WM	WATER METER
IC	INSPECTION COVER	WO	WASH OUT
IL	INVERT LEVEL	WT	WATER TAP
IRF	IRON RAIL FENCE	WV	WATER VALVE
KO	KERB OUTLET		
LB	LETTER BOX		
LP	LAMP POST		
MH	MAN HOLE		
O/H	OVERHEAD		
P	POST/POLE		
PF	PANEL FENCE		
	PEG/MARKER		
+ 12.34	SPOT LEVEL		

TREE WITH SPREAD & GIRTH
Top of Embankment
Bottom of Embankment
EMBANKMENT
STN 2 SURVEY STATION
—11.50— CONTOUR VALUE

Survey Station Schedule

Station	Easting	Northing	Level
S1	305101.142	206366.856	190.759
S2	305074.714	206363.636	189.849
S3	305078.365	206352.578	190.006
S4	305094.686	206358.544	190.752
S5	305101.722	206349.475	190.841
S6	305082.594	206337.975	190.201
S7	305126.840	206350.778	190.854
S8	305145.323	206333.745	190.869
S9	305125.040	206328.660	190.890
S10	305115.549	206320.194	190.990
S11	305129.939	206385.016	190.798
S12	305177.381	206337.665	191.148
S13	305106.490	206391.626	190.226
S14	305155.092	206404.596	191.214
S15	305154.265	206448.377	192.472
S16	305194.275	206432.695	200.260

SENIOR SURVEYS
LAND SURVEY CONSULTANTS

Contact Details:

Phil Senior
Unit 1E Chapel Barns
Merthyr Mawr
Bridgend
CF32 0LS
Tel: 07853240403
Email: Philseniorsurveys@Gmail.com

This drawing is copyright.Use or reproduction without prior permission of Senior Surveys Ltd is prohibited,Rights of the title are retained until all invoices are paid in full,Thank you.