



Site key

- Site Boundary
- 1.8 m High close boarded timber fence
- 1.8m High reclaimed stone or brick screen wall
- 1.8m high Ecoscape WPC Composite Fence Panel System in Charcoal
- Front garden hedge behind 900mm high black steel railings on reclaimed stone dwarf wall
- Indicates notional locations for new tree planting
- Indicates the removal of existing trees

Surfaces key

- Public realm hard surfacing materials
- Private realm hard surfacing materials
- SUDs bio retention feature
- Public realm soft landscaped areas
- Private front gardens
- Private rear gardens

For Landscaping details ,please refer to drawings by WYG Landscape consultants.

For proposed site & block levels and drainage & SuDs details, please refer to Engineers' drawings.

Tree key

- Crown Spread, Measured in North, South, East and West side of tree.
- Tree number, (T - Individual Tree, G - Group, A - Tree area, W - Woodland, H - Hedgerow)
- Root Protection Area (RPA) A layout design tool indicating the minimum area around a tree deemed to contain sufficient roots and rooting volume to maintain the tree's viability, and where the protection of the roots and soil structure is treated as a priority.
- Please refer to Tree Survey and report by Stephen Lucocq, ArBts - and their dwg: 12-03-20
- Tree mounted Bat Box
- Hibernation Bat Box
- Integrated Bat Box - Habitat 001
- Ridge Bat Access
- Integrated Bird Box - Habitat Terraced Sparrow Box
- Integrated Bird Box - Habitat 003 Swift Box
- 13 cm X 13 cm Hedgehog access gaps in fencing
- 1350mm x 1350mm Horseshoe bat cool tower within outbuilding style structure

For design details,please refer to drawings & reports prepared by David Clements Ecology consultants.

For typical Bat & Boxes locations on proposed house types, please refer to architects drawing 2447-(03)312.

Perimeter Boundary Treatments

- Existing stone wall & railings to be upcycled and rebuilt to accommodate the new vehicular access to the site
- Existing wall & railings to be upcycled and rebuilt to provide defined boundary between proposed site and Campsie House
- Existing wall & railings to be retained and made good
- Existing stone and brick walls to be retained, made good and rendered on the site side
- Existing stone retaining wall to be retained and made good
- Existing railings to the upper plateau to be retained in-situ and made good
- Existing stone retaining wall to be retained in-situ, made good and painted to match new composite fence
- Existing masonry wall to be retained in-situ, made good and painted to match new composite fence
- New close boarded timber fence
- New brick screen wall
- Existing wall & railings to be retained and made good
- Existing stone wall to be retained and made good
- Existing Listed building
- Existing wall & railings to be retained and made good

HOUSE TYPE SCHEDULE:

Social Rent:

F	1b Flat	14 No.
G/1	2b Bungalow	2 No.
G/2	2b Bungalow	1 No.
H	2b House	8 No.
J	3b House	4 No.
K	4b House	2 No.

Sub-total: 31 No.

Open Market:

B	2b House	6 No.
C	3b House	15 No.
D	3b House	6 No.
E	3b House	4 No.
Plot 1 2b 'Cottage'	1 No.	
Flat Conversions	7 No.	

Sub-total: 39 No.

TOTAL: 70 No.

Ecological key

- Tree mounted Bat Box
- Hibernation Bat Box
- Integrated Bat Box - Habitat 001
- Ridge Bat Access
- Integrated Bird Box - Habitat Terraced Sparrow Box
- Integrated Bird Box - Habitat 003 Swift Box
- 13 cm X 13 cm Hedgehog access gaps in fencing
- 1350mm x 1350mm Horseshoe bat cool tower within outbuilding style structure

For design details,please refer to drawings & reports prepared by David Clements Ecology consultants.

For typical Bat & Boxes locations on proposed house types, please refer to architects drawing 2447-(03)312.

This drawing is copyright and its use or reproduction without the permission of Spring Design Consultancy Limited. All rights are reserved until invoices are paid in full. No responsibility will be taken for any design used for construction prior to receipt of relevant approvals.

rev	date	description	by
A	14.10.2020	New composite fence panel system proposed in lieu of c.b timber fence to comply with Planning requirements. Bird & Bat boxes located as per DCE drawing.	WWM
B	05.11.2020	Additional ecological notes added	SC
C	11.11.2020	Enhancement for Horseshoe bats revised as per David Clements Ecology revised report	WWM
D	04.12.2020	900mm railings fence line revised to be in different line style & colour	WWM

Status:

Planning

Drawn: WWM
Director: JM
Date: July 2020
Scale: 1:500 @ A1

Client: Coronado
Project: St Tydfil's Hospital Site, Merthyr Tydfil
Title: Proposed Site Layout
Ref: 2447-00(03)101

Rev: D