



 Site Boundary
 Existing trees/vegetation to be retained
 Existing trees/vegetation to be removed

Indicative Location of Tree Protection Fencing (Arboricultural Method Statement and Tree Protection Plan to be prepared for construction)

Where enabling / construction works are likely to be within Root Protection Areas (RPAs), reference shall be made to an Arboricultural Method Statement. The Arboricultural Method Statement shall be prepared to inform the appropriate mitigation measures during the construction phase. This may include hand digging within the RPAs, or watch briefs by an arboriculturist during of construction within RPAs.

P01	10/09/2024	FOR INFORMATION	MM	JM	V
Rev.	Date	Description	By	Chk'd	Ap

Drawing Status	Suitability
FOR INFORMATION	
S2	
AtkinsRéalis 	2 Capital Quarter, Tyndall St, Cardiff CF10 4BZ Tel: +44 (0)1454 662000 Fax: +44 (0)1454 663333 www.atkinsglobal.com

MERTHYR TYDFIL
COUNTY BOROUGH COUNCIL

Project Title				
YSGOL RHYD Y GRUG				
Drawing Title				
EXISTING SITE AND TREE REMOVAL PLAN				
Scale	Designed	Drawn	Checked	Authorised
1:250	MM	MM	JM	WR
Original Size	Date	Date	Date	Date
A1	30/08/24	30/08/24	30/08/24	30/08/24
Drawing Number				Revision
RYF-ATR-XX-XX-D-L-480001				P01