

SW MANHOLE SCHEDULE

MH REF.	COVER LEVEL	INVERT LEVEL	PROPOSED DEPTH TO SOFFIT (m)	PIPE DIA. IN/OUT (mm)	MANHOLE TYPE	MANHOLE DIAMETER	COVER GRADE	COORDINATES		NOTES
								EASTING	NORTHING	
S1	133.70	132.88	0.670	150/150	TYPE 3	450	B125			
S2	133.75	132.71	0.890	150/150	TYPE 3	450	B125			
S3	133.75	132.56	1.040	150/150	TYPE 3	450	B125			
S4	133.30	132.30	0.850	150/150	TYPE 3	450	D400			
S5	133.23	132.13	0.950	150/150	TYPE 3	450	B125			
S6	133.15	131.57	1.430	150/150	TYPE 2	1200	B125			CATCHPIT
S7	133.15	131.50	1.425	150/150	TYPE 2	1200	B125			HYDROBRAKE - FLOW CONTROL CHAMBER
S8	132.82	131.37	1.225	150/150	TYPE 3	450	B125			
S9	133.10	131.15	1.800	150/150	TYPE 2	1200	B125			
S10	133.43	130.99	2.290	150/150	TYPE 2	1200	B125			
S11	133.75	133.00	0.600	150/150	TYPE 3	450	B125			
S12	133.70	132.86	0.690	150/150	TYPE 3	450	B125			
S13	133.41	132.75	0.560	100/100	TYPE 3	450	D400			

FW MANHOLE SCHEDULE

MH REF.	COVER LEVEL	INVERT LEVEL	PROPOSED DEPTH TO SOFFIT (m)	PIPE DIA. IN/OUT (mm)	MANHOLE TYPE	MANHOLE DIAMETER	COVER GRADE	COORDINATES		NOTES
								EASTING	NORTHING	
F1	133.75	132.93	0.720	100/100	TYPE 3	450	B125			
F2	133.67	132.75	0.820	100/100	TYPE 3	450	B125			
F3	133.62	132.70	0.820	100/100	TYPE 3	450	B125			
F4	133.50	132.90	0.500	100/100	TYPE 3	450	B125			
F5	133.50	132.81	0.590	100/100	TYPE 3	450	B125			
F6	133.45	132.68	0.670	100/100	TYPE 3	450	B125			
F7	133.45	132.59	0.760	100/100	TYPE 3	450	B125			

FW INSPECTION CHAMBER SCHEDULE

MH REF.	COVER LEVEL	INVERT LEVEL	PROPOSED DEPTH TO SOFFIT (m)	PIPE DIA. IN/OUT (mm)	MANHOLE TYPE	MANHOLE DIAMETER	COVER GRADE	COORDINATES		NOTES
								EASTING	NORTHING	
IC.F1	133.75	133.95	0.700	100/100	TYPE 3	450	B125			ODOUR SEALED COVERS
IC.F2	133.75	133.95	0.700	100/100	TYPE 3	450	B125			ODOUR SEALED COVERS

THIS DRAWING IS COPYRIGHT © CAMBRIA CONSULTING LTD.
DO NOT SCALE FROM THIS DRAWING.

CONTRACTORS MUST CHECK ALL DIMENSIONS ON SITE. ONLY FIGURED DIMENSIONS ARE TO BE WORKED FROM. DISCREPANCIES MUST BE REPORTED IMMEDIATELY TO CAMBRIA CONSULTING LIMITED BEFORE PROCEEDING.

THE CONTRACTOR IS TO REFER TO THE SPECIFICATION, FULL SCHEDULE OF RESIDUAL RISKS IN THE CONTRACT DOCUMENTATION AND ALSO TO INFORMATION FROM OTHER DESIGNERS, IN PARTICULAR THE M&E CONSULTANT REGARDING EXISTING LIVE SERVICES.



THIS SYMBOL IS USED TO HIGHLIGHT INSTANCES OF RISK WITHIN THE CONSTRUCTION PROCESS.
ALWAYS CHECK FOR LATER REVISIONS OF THIS DRAWING.

P02	TYPE 4 CHAMBERS CHANGED TO TYPE 3. SIC CHAMBERS REMOVED. COORDINATES REMOVED.	BW	BW	BW
			08/11/24	
P01	STAGE 3 ISSUE.	PY	BW	JB
			05/09/24	
Rev.	Description	By	Chk	App

Client:



Cynghor Bwrdeistref Sirol
MERTHYR TYDFIL
County Borough Council

Project:

YSGOL RHYD Y GRUG

Drawing Title:

PROPOSED DRAINAGE
MANHOLE SCHEDULE

Drawing No.

RYG CAM ZZ XX DR C 1107

Project	Originator	Vol.	Level	Type	Role	Number
---------	------------	------	-------	------	------	--------

Status:	Scale @A1:	Rev.
SS PRELIMINARY	N/A	P02



CAMBRIA
Constructive Thinking

Civil & Structural Engineers
Cambria House
16 Plas St. Pol de Leon
Penarth Marina
Cardiff, CF64 1TR

T 029 2009 3333
E admin@cambria.co.uk
W www.cambria.co.uk
@cambriauk
uk.linkedin.com/in/cambriauk