

Shrub Screen -Native Shrub Mix - 200m²

No.	%	Species	Size(mm)	Rootzone
60	15	Acer campestre	60-80	1+1 B
60	15	Corylus avellana	60-80	1+2 B
80	20	Crataegus monogyna	80-100	1+1 B
20	5	Ilex aquifolium	40-60	3L B
21	5	Lonicera periclymenum	60-80	1+1 C
40	10	Prunus spinosa	80-100	1+2 B
20	5	Rosa canina	60-80	1+1 B
40	10	Sambucus nigra	80-100	1+1 B
40	10	Viburnum opulus	60-80	1+2 B
400	100%			

Planting at 2 plants / m²
Shrub screen mix to be planted in 400mm deep approved topsoil and with 75mm deep bark mulch

Note: 200m² mix is for overall site spread, for this application only 15sqm of new planting is pproposed. Bat boxes installed under previous application.



Key

- Existing concrete surfacing retained and jet washed to remove surface dirt and laitance - 22m²
- Existing tarmac surfacing retained with holes, cracks and surface irregularities made good - 290m²
- Existing grass areas retained

- New native mix shrub screen - 200m²
- New ornamental shrub planting - 90m²
- Existing paving removed and replaced with new 450x450x50mm Tobermore Standard flags 180m² - colour TBC
NB: All paving to entrances to be ramped to existing FFL.

- Existing paving slabs retained and jet washed to remove surface dirt and laitance - 70m²
- New Hawthorn hedge
- New tree planting
- Bin Store
- New Sprinkler Tank Store

NOTE:
m² shown is for entire scheme