1 Site - GA-200
1 : 200

2 Site - GA Key
1 : 200

SURFACING

- P1 Asphalt road and yard engineers details
- P2 Black Asphalt footpath and playground to engineers details
- P3 Contrasting coloured asphalt to rear ramps to engineers detail
- P4 20-15-90/135 PCC slab paving
- P5 20-15-90/135 PCC corduroy hazard tactile slab to top and bottom of steps
- P6 Concrete slab to engineers detail
- P7 Accessible parking bay markings, hatch and disabled logo in yellow thermoplastic
- P8 20-15-35/152 Wetpour rubber safety surface
- P9 20-15-90/170 PCC permeable unit paving
- P10 45-55-55/351 Play bark with timber edging
- P11 Reinforced grass Gridforce GF40 to engineers details
- P12 Artificial grass to engineers details

KERBS AND STEPS

- K1 20-85-45/185 PCC HB2 kerb
- K2 20-85-45/185 PCC Bn flush kerb
- K3 2085-45/145 PCC EF pin kerb
- ST 30-05-25/135 PCC steps with inbuilt tread and riser highlights

BOUNDARIES

COLOUR NOTE: All new fences to be black

- BW New brick retaining wall with stone coping
- IC New In situ concrete retaining wall with parapet
- CW Existing concrete block wall (nom1.8m) -chain link removed.
- S1 Existing stone wall (nom 2m)- chain link removed.
- S2 Existing stone wall (nom 0.75m)-Existing steel railings on wall retained/ repaired. Wall repaired.
- S3
- SW New stone faced retaining wall
- F1 25-20-30/145 1.8m high weldmesh fence
- F5 25-20-30/145 2.4m high weldmesh fence
- F2 25-20-30/161 1.5m high bowtop fence
- F4 25-20-30/161 1.8m high self adjusting railings
- Ac Anti-climb extention to railing post to discourage access to top of wall Finish and colour to match adjacent fence F4
- F6 25-20-30/109 Timber diamond rail kneerail
- F7 25-20-30/117 Timber palisade screen fence to play area
- F8 25-20-30/115 Timber screen fence to bin compound
- F9 25-20-30/161 0.9m high bowtop fence
- F10 25-20-30/149 3m high ball stop fence to MUGA
- F11 Smooth planed timber close board fence to LRB /Pre-School play areas - smooth clad face to internal side. 1.8m high
- Gp 25-60-35/109 Steel swing gates. Single pedestrian gate infill to match adjacent fence
- Gt 25-60-35/109 Timber gate to Forest Scools area
- Gv 25-60-35/109 Steel swing gates Double vehicular gate infill to match adjacent fence

All existing chainlink fencing to be removed

STREET FURNITURE and FITTINGS

- Csh 35-70-75/165 Cycle shelter with Sheffield Hoops
- Bo 25-20-85/110 Bollards
- Dp 25-20-85/110 Disabled parking sign on steel post at head of bay
- Dh 25-25-60/130 Door protection hoop to all outward opening doors
- Hr 25-25-10/135 Handrails to both sides of ramps and steps
- Pe 35-35-55/105 Play equipment
- Cs 35-70-75/115 Canopy- Shade sail
- Rp 45-40-60/430 Raised Timber Bed
- Se xxx Seat- TBC

SOFT LANDSCAPE

- Ag 40-35-35/135 Amenity grass seeding on 150mm approved topsoil
- Wf 40-35-35/130 Wildflower seeding on low fertility sub soil
- Op 40-35-00/175 Ornamental planting bed on 400mm approved topsoil
- Np 40-35-00/175 Native shrub mix planting bed on 400mm approved topsoil
- Nh 40-35-00/175 Native hawthorn hedge in 400mm deep approved topsoil trench
- Bu Bulb planting area
- Tp 40-35-00/170 New tree planting in prepared topsoil tree pit

North

The drainage and site levels strategy has been developed by CB3.
ASL drawings reflect CB3's design information and ASL cannot take responsibility for their drainage design

The parking and road designs and site levels strategy has been developed by CB3.
ASL drawings reflect CB3's design information and ASL cannot take responsibility for their design

Rev	Description	Drawn	Checked	Date Issued
P6	Fence colours added	CM/KT		17.01.20
P8	Fence colours added	CM/KT		03.03.20
P10	Boundary fence spec adjustments	CM		04.6.20
P11	fire hydrants added	CM		200714
P12	north entrance planting added	CM		200805
C0	Planning Application Amendments	CM		201016
C1	Construction Issue	CM		201027
C2	Reinforced grass added, new wall extended	CM		15.12.20
C3	Planning Application Issue	CM		12.01.21
C4	ball stop fence to MUGA, additional shade sail canopy, reinforced grass added			12.03.21
C5	LRB and Pre school areas added	CM		26.04.21
C6	Final Construction Issue	CM		13.9.21

DO NOT SCALE. Use figured dimensions only. All dimensions to be checked on site. Any discrepancies before the work is put in hand. CAD copyrights Austin-Smith:Lord LLP

This drawing must only be used for the purpose for which it is supplied and its contents must not be published for any purpose without written permission.
No areas indicated, or areas calculated from this drawing should be relied upon for measurement or as the basis for development contracts.
Austin-Smith:Lord LLP is a limited liability partnership registered in England & Wales. Number OC315362

Drawn	Author
Date	Issue Date
Scale @ A0	1 : 200
Status	CR

Austin-Smith:Lord LLP
Architects Designers Planners
Landscape Architects
Cambrian Bakery Drive
Cardiff
CF11 0SN
t +44 (0)2920 225 208

e cardiff@austinsmithlord.com

Drawings and models powered by Austin-Smith:Lord LLP **BIM** using AutoDesk **Revit**

Austin·Smith:Lord

Project Ysgol Y Graig, Merthyr Tydfil

Description School Site -External Works General Arrangement

Job No.	Drawing No.	Revision
119005	YYG- ASL- 00- XX- DR- L- 9010	C6