




**RHS of Front Main  
Entrance Elevation**

**West (Front) Elevation**

- ① Roof to be re-slatted with natural slates on timber battens and breathable underlay to provide suitable ventilation to cold roof space. Remaining existing slates to be salvaged and re-used where possible.
- ② Gable parapets, copings and corbels to be made good and restored using matching natural stone, reclaimed from the site where possible and lime mortar. Code 4 lead flashings to be used at all parapet abutments.
- ③ Existing finial to be made good using matching materials
- ④ Timber fascias to be replaced to match existing and rainwater goods to be renewed where necessary using matching cast iron replacement gutters and downpipes
- ⑤ New painted hardwood double doors to main entrance

- ⑥ Existing timber sash windows to be repaired and retained where possible or otherwise replaced to match. Secondary glazing will be applied internally to improve thermal and acoustic performance
- ⑦ Stone tracery to be glazed with slimline, double glazed metal window frames. Remnants of existing metal windows to be removed. Remaining stained glass bullseyes and daggers to be retained
- ⑧ All timber windows, doors and fascias to be painted in RAL 7016 Anthracite Grey
- ⑨ Metal window frames to be factory finished in RAL 7016 Anthracite Grey
- ⑩ Redundant vents and other openings to be made good using reclaimed stone and lime mortar
- ⑭ Existing cupola to be made good using matching materials

-  Redundant windows in non-listed retained link element to be blocked and rendered over
-  Crittall W20 steel windows with bottom hung inward opening casements
-  Crittall W20 steel windows with side hung outward opening casements
-  Crittall W20 steel windows with side hung outward opening casements & fixed arched pane above

**Status: PLANNING**

This drawing is copyright and its use or reproduction without the permission of Spring Design Consultancy Limited. All rights are reserved until invoices are paid in full. No responsibility will be taken for any design used for construction prior to receipt of relevant approvals.

| rev | date     | description                                                         |
|-----|----------|---------------------------------------------------------------------|
| A   | 17.08.20 | Existing fenestration updated following the survey + notes revised. |

|     |           |           |          |                                     |
|-----|-----------|-----------|----------|-------------------------------------|
| by  | Drawn:    | JM        | Client:  | Coronado                            |
| WWM | Director: | JM        | Project: | St. Tydfil's Hospital Site, Merthyr |
|     | Date:     | July 2020 | Title:   | Conversion West (Front) Elevation   |
|     | Scale:    | 1:100@A3  | Ref:     | 2447-(03)310-1                      |
|     |           |           | Rev:     | A                                   |

**spring**  
design

Unit 2 Chapel Barns | Merthyr Mawr  
Bridgend | CF32 0LS | 01656 656267  
mail@spring-consultancy.co.uk