

Naturalistic Woodland Planting Mix:

c. 650m.sq All @ 2.0m Centres

Canopy Species (30% by number):
50 Sorbus aucuparia 50 %
30 Betula pubescens 30 %
20 Salix caprea 20 %

Understorey & Edge Species
(70% by number):

56 Salix cinerea 25 %
90 Crataegus monogyna 40 %
33 Corylus avellana 15 %
33 Rosa canina 15 %
12 Ilex aquifolium 5 %

Naturalistic Woodland Planting Mix:

c. 860m.sq All @ 2.0m Centres

Canopy Species (30% by number):
65 Sorbus aucuparia 50 %
40 Betula pubescens 30 %
26 Salix caprea 20 %

Understorey & Edge Species
(70% by number):

75 Salix cinerea 25 %
120 Crataegus monogyna 40 %
45 Corylus avellana 15 %
45 Rosa canina 15 %
15 Ilex aquifolium 5 %

Naturalistic Woodland Planting Mix:

c. 500m.sq All @ 2.0m Centres

Canopy Species (30% by number):
38 Sorbus aucuparia 50 %
22 Betula pubescens 30 %
15 Salix caprea 20 %

Understorey & Edge Species
(70% by number):

44 Salix cinerea 25 %
70 Crataegus monogyna 40 %
26 Corylus avellana 15 %
26 Rosa canina 15 %
9 Ilex aquifolium 5 %

Notes on Existing Trees
In the following is provided for ease of reference. For further refer to the Tree Report by ArbTs / Stephen Lucocq October 2019

T1 Norway Spruce RETAIN
T2 Hawthorn REMOVE
T4 Ash RETAIN
T5 Hawthorn RETAIN
T6 Hawthorn RETAIN
T7 Hawthorn RETAIN
T8 Hawthorn RETAIN
T9 Hawthorn REMOVE
T10 Hawthorn REMOVE
T11 Hawthorn REMOVE
T12 Hawthorn RETAIN
T13 Hawthorn REMOVE
T14 Hawthorn RETAIN
T15 Hawthorn RETAIN
T16 Hawthorn RETAIN
T17 Hawthorn REMOVE
T931 Sycamore RETAIN
T932 Sycamore RETAIN
T933 Hawthorn REMOVE
T934 Hawthorn REMOVE
T935 Hawthorn RETAIN
T936 Sycamore RETAIN
T937 Sycamore RETAIN
T938 Ash RETAIN

H1 Leyland Cypress Hedge REMOVE
H2 Leyland Cypress Hedge REMOVE

G1 Sycamore Hazel Ash Hawthorn REMOVE
G2 Ash RETAIN (Remove as shown)
G3 Ash RETAIN (Remove as shown)
G4 Hawthorn RETAIN
G5 Ash / Hawthorn RETAIN
G6 Ash RETAIN
G7 Hawthorn RETAIN

Hedgerow (c.86 lin.m)
Planted at 4 plants per lin.m

210 Crataegus monogyna (60%)
110 Corylus avellana (30%)
35 Ilex aquifolium (10%)

Bulbs (c.80m.sq)
Planted @ 50 per m.sq
4000 Narcissus
pseudonarcissus (Bulbs)

Hedgerow (c.98 lin.m)
Planted at 4 plants per lin.m

235 Crataegus monogyna (60%)
120 Corylus avellana (30%)
40 Ilex aquifolium (10%)

KEY

Application Boundary
(Approx only)

Existing
Trees / Woodland

Trees REMOVED
(Refer to Tree Report)

New
Woodland

Specimen
Trees

New
Field Hedgerows

Rain Gardens

Landscape Areas

Pathways Width Varies
(Timber edged gravel paths)

Stone Walls

Underground
Drainage Features

Linear Bio-retention features
(Width varies Ref Eng Drgs)

Rubble Pile
(Habitat creation: refer to ecologist report for further details)

Issue 4 July 2023 FOR PLANNING ONLY

(Landscape Layout updated to accommodate revisions by others)

Issue 3 February 2023 FOR PLANNING ONLY

(Landscape Layout updated to accommodate revisions by others)

Issue 2 February 2021 FOR PLANNING ONLY (SUDS / SABS REVISIONS)

Issue 1 June 2020 FOR PLANNING ONLY

John Campion Associates

Landscape Architecture * Landscape Planning * Urban Design

2 Redwood Drive, Clun Road, Aston on Clun, Nr Craven Arms, Shropshire SY7 8EZ

Client WDL Homes Ltd

Project Land at Crabtree Walk, Trefechan

Drg. Title Overall Landscape Layout

Date July 2023

Scale: 250 @ A0

Drg Nr:1909TMT.02

Drawn JCR/KR

Issue: 04

Note:

RG Existing Grassland
Retained in situ

