NOTES

1. This drawing is copyright.
2. All dimensions are to be checked prior to construction or manufacture. Any discrepancy to be reported to the Engineers immediately.
3. Do not scale this drawing, work to figured dimensions only.

EMBANKMENT SUBJECT TO RE-GRADING WORKS

PROPOSED SURFACE WATER DRAINAGE FROM DEVELOPMENT SITE TO DISCHARGE TO EXISTING WATER COURSE SUBJECT TO APPROVAL FROM AND AGREEMENT WITH M.T.C.B.C. DRAINAGE

FLOW CONTROL CHAMBER

HEADWALL STRUCTURE

3.0m FOOTPATH

MTCBC STREET LIGHTING SPECIFICATIONS.

- COLUMNS TO BE 6MTR ALC 6000 SERIES ALUMINIUN HOCKYSTICK WITH 0.3 OUT REACH LANTERN TO BE A TRT MINI ASPECT 35WATT FITTED WITH A 7 PIN NEMA SOCKET AND A DATEK CMS MONITORING NODE (PLEASE LIAISE WITH MTCBC STREET LIGHTING WHEN INSTALLING.
- DUCTING BOXES TO BE 450 X 450 IDS WITH COMPOSITE LED OR SIMULER.
- CABLES TO BE 10MM 3 CORE SWA.
- FEEDER PILLAR TO BE 12 X 6 MILD STEEL AS PER CHARLES ENDIRECT.

SECTION 38 PLAN KEY

- CARRIAGEWAY CONSTRUCTION TO STANDARD DETAILS
- FOOTWAY VEHICLE CROSSOVER CONSTRUCTION TO STANDARD DETAILS
- S38 HIGHWAY AGREEMENT BOUNDARY
- SURFACE WATER DRAINAGE SYSTEM

REV	DATE	BY	DESCRIPTION
D	12 FEB 2024	ov	ZEBRA CROSSING DELETED IN ACCORDANCE WITH MTCBC HIGHWAYS
C	25 JAN 2024	ov	STREET LIGHTING ADDED
B	9 JAN 2024	ov	SHADING ADJUSTED IN ACCORDANCE WITH MTCBC HIGHWAYS INSTRUCTIONS & LAYOUT UPDATED
A	23 AUG 2023	ov	LAYOUT UPDATED TO ARCH PLAN AL(90)02_AE & FFL'S TO PLOTS 23-25 ADJUSTED

REVISIONS

SMART ASSOCIATES
Consulting Civil & Structural Engineers
32 Lambourne Crescent
Cardiff Business Park
Llanishen, Cardiff
CF14 5GG
TEL: 029 20754321

MERTHYR VALLEYS HOMES

Project Title	DEVELOPMENT AT SWANSEA ROAD MERTHYR TYDFIL
Drawing Title	SECTION 38 : ADOPTION PLAN
Scales	1:250 @ A1
Drawn	ov
Checked	
Date	JUN 2023
Client	MERTHYR VALLEYS HOMES
Architect	C2J ARCHITECTS
Drawing Number	S.7810-S38-003
REV	D