Existing Grass
Existing Trees and Vegetation
Schwegler 1FF Bat Box at fixed high level
Proposed Grass Areas
Planting Bed
Rain Garden
Proposed Trees
Gabion Fence
Green Cycle Shelter
NHBS Sparrow Terrace or Schwegler 1SP Sparrow Terrace Bird Box at fixed high level

MKR : PANT INDUSTRIAL ESTATE : PLANTING SCHEDULE					
08/07/2020 rev 21 July 2020					
TREES			All trees are to be rootballed		
Carpinus betulus Fastigiata		Fastigiate Hornbeam	14-16cm Extra Heavy Standard	6	No
Crataegus mongyna		Hawthorn	12-14cm Heavy Standard	4	No
Malus sylvestris		Crabapple	12-14cm Heavy Standard	2	No
TOTAL				12	No
PLANTING BEDS 1-10		Bark Mulch to beds		131	m2
Crataegus mongyna	Cm	Hawthorn	60-80cm 1 + 1 Bareroot	51	No
Cornus sanguinea	Cs	Dogwood	60-80cm 1 + 1 Bareroot	35	No
Hedera helix	HH	Ivy	60-90cm 2Lpot	420	No
Ilex aquifolium	Ia	Holly	30-45cm 3Lpot	102	No
Polystichum setiferum	Poly	Evergreen Fern	2Lpot	12	No
Viburnum opulus	Vo	Guelder Rose	60-80cm 1 + 1 Bareroot	15	No
TOTAL				635	No
WILDFLOWER PLUGS					
Geranium pratense	Gp	Cranesbill	65cc Jumbo Plug	119	No
Potentilla reptans	Pr	Creeping cinquefoil	65cc Jumbo plug	86	No
TOTAL				205	No

CA 2020-46 Rev A
21 July 2020
Revised Planting

Corscadden Associates
77 Fairleigh Road
Pontcanna, Cardiff. CF11 9JW
Tel 02920 373053

email ca@corscaddenassociates.com

MKR PROPERTY PANT INDUSTRIAL ESTATE. MERTHYR TYDFIL

Drawing Title
LANDSCAPE PLANTING DETAILS

Scale: 1:250 at A1
Date: 8 July 2020

Drawing No: 291
CA 2020-46 Rev A