


# Mini Stonewold

A flat concrete slate that can be laid at pitches as low as 17.5° in both new build and reroofing projects.

## KEY ADVANTAGES

- Low pitch capability
- Quick, simple installation reduces laid costs
- Range of seven natural colours



## PRODUCT DETAILS

|                                                                 |                                                                                                                                                                                                                              |
|-----------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| <b>Size (overall)</b>                                           | 418 x 334mm                                                                                                                                                                                                                  |
| <b>Minimum Pitch and Headlap</b>                                | 17.5° at 100mm headlap / 22.5° at 75mm headlap<br>(The minimum pitch is based on a maximum rafter length of 10 metres. For rafter lengths greater than this, please contact the Technical Solutions Hotline on 03708 702595) |
| <b>Maximum Pitch (subject to fixing specification)</b>          | 90°                                                                                                                                                                                                                          |
| <b>Minimum Headlap</b>                                          | 75mm                                                                                                                                                                                                                         |
| <b>Maximum Headlap</b>                                          | 125mm                                                                                                                                                                                                                        |
| <b>Minimum Gauge/Batten Spacing</b>                             | 293mm                                                                                                                                                                                                                        |
| <b>Maximum Gauge/Batten Spacing</b>                             | below 22.5° 318mm / 22.5° and over 343mm                                                                                                                                                                                     |
| <b>Hanging Length (approx.)</b>                                 | 397mm                                                                                                                                                                                                                        |
| <b>Cover (all figures are net and do not allow for wastage)</b> |                                                                                                                                                                                                                              |
| Linear cover of 1 slate                                         | 294mm                                                                                                                                                                                                                        |
| Covering capacity                                               | 10.7 slates/m <sup>2</sup> at 318mm gauge / 9.9 slates m <sup>2</sup> at 343mm gauge                                                                                                                                         |
| <b>Weight</b>                                                   | 55kg/m <sup>2</sup> at 318mm gauge / 51kg/m <sup>2</sup> at 343mm gauge                                                                                                                                                      |
| per pallet, including pallet (approx.)                          | 1.16 tonnes                                                                                                                                                                                                                  |
| per 1000                                                        | 5.11 tonnes                                                                                                                                                                                                                  |
| <b>Battens Required (at max. gauge)</b>                         | 2.92m/m <sup>2</sup>                                                                                                                                                                                                         |
| <b>Batten Size</b>                                              |                                                                                                                                                                                                                              |
| Rafter centres up to 450mm                                      | 38 x 25mm                                                                                                                                                                                                                    |
| Rafter centres up to 600mm                                      | 50 x 25mm                                                                                                                                                                                                                    |
| <b>Fixing Clips</b>                                             | Eaves, Verge, Valley & Slate Clips                                                                                                                                                                                           |
| <b>Nail Size for Slates**</b>                                   | 50 x 3.35mm (A/A)                                                                                                                                                                                                            |
| <b>Pallet Quantities</b>                                        | Slates per pallet 216 / Slates per pack 36 / Packs per pallet 6                                                                                                                                                              |

\*All weights nominal \*\* (A/A) Aluminium Alloy

## FITTINGS & ACCESSORIES

### VERGE

Ambi-Dry Verge  
Rapid Verge

### HIP PRODUCTS

Universal Angle Hip  
Dry Hip  
Rapid Hip

### VALLEY PRODUCTS


GRP 125 Valley  
Dry Valley

### RIDGE PRODUCTS

Universal Angle Ridge  
Universal Angle Monoridge

### VENTILATION SYSTEMS

RedVent EavesVent  
RedVent 25 Over-Fascia Vent  
Rapid EavesVent  
Top Edge Abutment Ventilation  
DryVent Ridge  
Rapid Vented Ridge  
Uni-Vent Rapid Ridge/Hip  
DryVent Monoridge  
RedLine Ventilation Tile  
Rapid Roof Vent  
8.8k ThruVent Tile



# Mini Stonewold Product Codes

## TILES

|                 |      |
|-----------------|------|
| Standard Slate  | 4261 |
| Half Slate Pair | 4263 |

## UNDERLAYS

|                           |      |
|---------------------------|------|
| Spiritech 400 2S underlay | 9202 |
| Divoroll Elite 2S         | 9157 |
| Divoroll Universal 2S     | 9156 |

## EAVES PRODUCTS

|                                  |      |
|----------------------------------|------|
| RedVent EavesVent 350-450mm (6m) | 9189 |
| RedVent EavesVent 450-600mm (6m) | 9190 |
| Extension Trays 350-450mm (6m)   | 9498 |
| Extension Trays 450-600mm (6m)   | 9499 |
| Rapid EavesVent 2-in-1 Tray      | 9988 |
| Rapid EavesVent Rafter Roll (6m) | 9984 |
| RedVent 25 Over-Fascia Vent (6m) | 9593 |
| Underlay Support Tray (1.5m)     | 9076 |

## VERGE PRODUCTS

|                                        |      |
|----------------------------------------|------|
| DryVerge (Pack of 18 LH & 18 RH)       | 9390 |
| DryVerge Gable End Pack                | 9880 |
| Rapid DryVerge (Pack of 18 LH & 18 RH) | 9391 |
| Rapid DryVerge Gable End Pack          | 9881 |

## HIP PRODUCTS

|                                          |      |
|------------------------------------------|------|
| Dry Hip (2.7m)                           | 9046 |
| Continuous Hip (5m)                      | 9028 |
| Uni-Vent Rapid Ridge/Hip (10m)           | 9313 |
| Uni-Vent Rapid Hip Support Tray (1.2m)   | 9069 |
| Universal Angle Hip/Ridge Junction       | 9520 |
| Universal Angle Hip (without nail holes) | 7777 |
| Universal Angle Hip (with nail holes)    | 7778 |
| Hip Iron                                 | 9258 |
| Universal Angle Block-End Hip            | 7779 |
| Mortar Bedded Fixing Kit                 | 9314 |

## VALLEY PRODUCTS

|                               |      |
|-------------------------------|------|
| GRP 125 Valley (3m)           | 9595 |
| Dry Valley (Low Profile) (3m) | 9575 |
| Universal Valley Trough Tile  | 7175 |

## ABUTMENT PRODUCTS

|                                         |      |
|-----------------------------------------|------|
| Wakaflex Rapid Flashing                 |      |
| Top Edge Abutment Ventilation Pack (3m) | 9548 |
| Abutment GRP Secret Gutter (3m)         | 9596 |
| Bonding Gutter (Low Profile) (3m)       | 9580 |
| Bonding Gutter (High Profile) (3m)      | 9578 |

## RIDGE PRODUCTS


|                                        |      |
|----------------------------------------|------|
| DryVent Ridge (2.7m)                   | 9059 |
| Uni-Vent Rapid Ridge/Hip (10m)         | 9313 |
| Continuous Ridge (5m)                  | 9308 |
| Ridge Vent Terminal                    | 7254 |
| Terminal Adaptor                       | 9175 |
| Flexible Pipe (100 to 100mm)           | 9172 |
| Gas Flue Ridge Terminal                | 7242 |
| Gas Flue Extension Adaptor             | 9143 |
| Gas Flue Blanking Plates               | 9099 |
| Universal Angle Ridge                  | 7146 |
| Hi-Pitch Universal Angle Ridge         | 7151 |
| Universal Angle Block-End Ridge        | 7518 |
| DryVent Monoridge (2.7m)               | 9084 |
| Universal Angle Monoridge              | 7148 |
| Universal Angle Block-End Monoridge LH | 7297 |
| Universal Angle Block-End Monoridge RH | 7298 |
| Universal Angle Monoridge End Cap LH   | 9778 |
| Universal Angle Monoridge End Cap RH   | 9779 |
| Mortar Bedded Fixing Kit               | 9314 |
| Universal Angle Ridge End Cap          | 9773 |

## VENTILATION TILES

|                              |      |
|------------------------------|------|
| RedLine Vent Tile            | 9118 |
| 8.8k ThruVent Tile           | 7935 |
| Rapid Roof Vent Tile         | 9124 |
| Rapid Roof Vent Adaptor      | 9791 |
| Flexible Pipe (100 to 100mm) | 9172 |

## FIXING

|                                  |      |
|----------------------------------|------|
| Slate Clip                       | 9185 |
| Storm Clip and nails (100)       | 9530 |
| Verge Clip (25)                  | 9529 |
| Eaves Clip                       | 9186 |
| Slate and Eaves Clip Nails (812) | 9338 |
| Kro-Clip (50)                    | 9142 |
| Innofix Clip (500)               | 9824 |



BMI UK & Ireland  
BMI House,  
2 Pitfield, Kiln Farm,  
Milton Keynes, MK11 3LW  
+44 (0) 3705 601000

[www.bmigroup.com/uk](http://www.bmigroup.com/uk)

We are committed to continuously enhancing and improving our product range. We reserve the right to change our product specifications. We reserve the right to correct any typographical or clerical error or omission. For the latest information contact customer service.