



Tree Work Schedule			
No.	Species	Works	Category
G03	Various	Plans: to achieve 1.5m construction access	B2
T06	Common Oak	Plans: crown lift to achieve 3m construction access	A1
T08	Sycamore	Plans: to achieve 1.5m construction access	B1
T09	Copper Beech	Fell: to ground level, grind stump	B1
T10	Copper Beech	Fell: to ground level, grind stump	C1

No. of individual trees to be removed			
U	A	B	C
0	0	1	1

Utility apparatus

Underground utility apparatus
Mechanical trenching for the installation of underground apparatus and drainage severs any roots present and can change the local hydrology in a way that adversely affects the health of the tree. For this reason,

Note: The RPA of tree T06 has been amended to reflect the likely root barriers.

Note: All hard surfacing and parking spaces are to be retained as existing.

